TAZAMA PIPELINES LIMITED

ADDENDUM / CORRIGENDUM ONE

SUPPLY AND DELIVERY OF SPLIT SLEEVES

CONTRACT NO: TPL-301-0725-PM-002

CLARIFICATIONS / CHANGES

Query	BIDDER'S QUERY	TAZAMA RESPONSE
1.0	We kindly request extension for the Closing Date due to Technical Consultations with Manufacturers that are critical before submission of the Bid	The Deadline for the Tender is extended to Thursday 11th September 2025 at 10:30 Zambian Time / 11:30 Tanzanian Time
2.0	What is the Maximum Allowable Operating Pressure (MAOP) of the lines?	MAOP of the line is around 1800 psi
3.0	What is the minimum and maximum design temperatures for the lines?	Min and Max temp are -20deg C to +80 deg Celsius.
4.0	What product is currently running through the lines, and is there any presence of H₂S?	Product running is Petroleum product gasoil and gasoline